

## Center Road Overlay - Phase 6

In July 2014, Jefferson County Public Works successfully completed overlaying 2.4 miles of Center Road with hot mix asphalt from milepost 4.4 to 6.8. The asphalt overlay rehabilitated and extended the service life of the existing pavement by eliminating surface distresses that can lead to pavement failure over time. The overlay also reduced pavement roughness and irregularities resulting in a better ride for drivers.



The newly rehabilitated asphalt surface and striping on Center Road provides an improved ride quality.

Lakeside Industries of Port Angeles, WA constructed the project for \$666,887. The project was 86.5 percent grant funded by the Federal Highway Administration and 13.5 percent funded by the Public Infrastructure Fund.

Center Road is a critical major collector road that transports residents, visitors and goods throughout Jefferson County. The 15.01-mile-long road connects the communities of Chimacum and Quilcene and provides access to State Routes 19, 101, and 104. Design and construction to rehabilitate another 2.26 miles of Center Road are planned for 2015—2017.



1. Sealed cracks in the existing pavement at the Eaglemount Road intersection with Center Road are visible indicators of distressed pavement. 2. Lakeside’s paving equipment train ready to begin paving. It took three days for Lakeside to pave the 2.4-mile-long project. 3. A 2-in asphalt mat was overlaid on top of existing pavement. 4. Compaction testing results on Center Road exceeded minimum standards, ensuring the longevity of the new pavement.